



WASHINGTON COUNTY, ARKANSAS

Purchasing Department

April 19, 2018

Addendum

Bid 2018-02 Blue Springs Road Bridge

Clarification to bid scope of work request:

1. Washington County shall provide:
 - a. Pre-excavation work at jobsite
 - b. Demolition of original bridge and materials
 - c. Road Closures and detours
 - d. Precast concrete topper, guard rails, and rebar materials.
2. Respondent shall provide:
 - a. All New H and K Wall sheet Piling Steel
 - b. Poured Cement
 - c. Labor and equipment for project
 - d. Price completion options for:
 - i. Washington County placing the pre-cast concrete bridge topper and completing the bridge
 - ii. Respondent placing the provided pre-cast concrete bridge topper and completion of the bridge.
3. **Page 18: Section 5-3 shall be updated to include additional price and size options.**
4. The 90 days labor shall remain set, if the respondent's awarded pricing is for the placement of the pre-cast concrete bridge topper and the completion of the bridge.
5. The shape and the width of the K Wall sheet piling may be variable. The height of the K Wall sheet piling is to set. The price and variable sizes shall be listed.
6. The H pile is to be 8inches or greater. The price and variable larger sizes shall be listed.
7. Redirection of the channel is not required.
8. If the respondent has additional contract terms and conditions:
 - a. Contract should be sent with the response to the bid packet.
 - b. The respondent shall submit an electronic copy to purchasing@co.washington.ar.us upon award of the bid.